

# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK\_INDENT54127

## APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/18/2022-23, Date: 04-11-2022

Name of Work:Improvements and maintenance of Footpath in ward No. 06 Kogilu

| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Unit | Approved Tender Rates of |                                                                                  |
|---------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|----------------------------------------------------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |      | VISHWANATH P ( )         |                                                                                  |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |      | In Figures               | In Words                                                                         |
| 1       | 338.88        | Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such similar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work.                                                                                                                                                                    | Cum  | 180.0                    | Rupees One Hundred Eighty Only                                                   |
| 2       | 56.48         | Providing and laying in position plain cement concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.                                                                                                                                                                                                                                                 | Cum  | 4700.0                   | Rupees Four Thousand Seven Hundred Only                                          |
| 3       | 107.82        | Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately) | Cum  | 5498.0                   | Rupees Five Thousand Four Hundred Ninety Eight Only                              |
| 4       | 6.47          | Supplying, Fitting and Placing TMT Fe550 bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Cum  | 79998.92                 | Rupees Seventy Nine Thousand Nine Hundred Ninety Eight and Ninety Two Paise Only |
| 5       | 308.07        | Providing and Fixing pre cast covering Slab 100mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Sqm  | 1734.0                   | Rupees One Thousand Seven Hundred Thirty Four Only                               |
| 6       | 338.88        | Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Cum  | 110.0                    | Rupees One Hundred Ten Only                                                      |
| 7       | 433.76        | Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | t.Km | 100.0                    | Rupees One Hundred Only                                                          |

Signature of the Contractor

Executive Engineer  
Byarayanapura Division  
BBMP, Bangalore - 92

ಬೃ.ಬಿ.ಮ.ನಾ., ಬೆಂಗಳೂರು